

---

# Contents

Abstract .....	iii
Acknowledgments .....	v
Report Contributors .....	vii
Summary .....	ix
1.0 Introduction .....	1.0-1
1.1 Purpose and Scope .....	1.0-1
1.2 Related Reports .....	1.0-2
1.3 Groundwater Remediation Project .....	1.0-2
1.4 Helpful Information .....	1.0-3
2.0 Groundwater .....	2.0-1
2.1 Overview of Hanford Site Groundwater .....	2.1-1
2.1.1 Groundwater Flow .....	2.1-1
2.1.1.1 March 2003 Water Table .....	2.1-2
2.1.1.2 Water-Table Changes from Fiscal Year 2002 .....	2.1-2
2.1.2 Groundwater Contaminants .....	2.1-3
2.1.3 Groundwater Remediation .....	2.1-4
2.2 100-BC-5 Operable Unit .....	2.2-1
2.2.1 Groundwater Contaminants .....	2.2-1
2.2.1.1 Strontium-90 .....	2.2-1
2.2.1.2 Tritium .....	2.2-2
2.2.1.3 Nitrate .....	2.2-2
2.2.1.4 Chromium .....	2.2-2
2.2.2 CERCLA Groundwater Monitoring .....	2.2-2
2.3 100-KR-4 Operable Unit .....	2.3-1
2.3.1 Groundwater Contaminants .....	2.3-2
2.3.1.1 Chromium .....	2.3-2
2.3.1.2 Tritium .....	2.3-3
2.3.1.3 Carbon-14 .....	2.3-5
2.3.1.4 Strontium-90 .....	2.3-5
2.3.1.5 Other Constituents .....	2.3-6
2.3.2 CERCLA Interim Remedial Action for Chromium .....	2.3-6
2.3.2.1 Progress During Fiscal Year 2003 .....	2.3-7
2.3.2.2 Influence on Aquifer Conditions .....	2.3-7
2.3.3 AEA Monitoring .....	2.3-8
2.4 100-NR-2 Operable Unit .....	2.4-1
2.4.1 Groundwater Contaminants .....	2.4-1
2.4.1.1 Strontium-90 .....	2.4-2
2.4.1.2 Tritium .....	2.4-2
2.4.1.3 Nitrate .....	2.4-2
2.4.1.4 Sulfate .....	2.4-2
2.4.1.5 Petroleum Products .....	2.4-3

2.4.1.6	Manganese and Iron .....	2.4-3
2.4.1.7	Chromium .....	2.4-3
2.4.2	CERCLA Interim Groundwater Remediation for Strontium-90 .....	2.4-4
2.4.3	RCRA Groundwater Monitoring .....	2.4-4
2.4.3.1	116-N-1 Liquid Waste Disposal Facility .....	2.4-5
2.4.3.2	120-N-2 Surface Impoundment and 120-N-1 Percolation Pond .....	2.4-5
2.4.3.3	116-N-3 Liquid Waste Disposal Facility .....	2.4-5
2.4.4	AEA Monitoring .....	2.4-5
2.5	100-HR-3-D Operable Unit .....	2.5-1
2.5.1	Groundwater Contaminants .....	2.5-1
2.5.1.1	Chromium .....	2.5-2
2.5.1.2	Strontium-90.....	2.5-2
2.5.1.3	Tritium.....	2.5-3
2.5.1.4	Nitrate .....	2.5-3
2.5.1.5	Sulfate .....	2.5-3
2.5.2	CERCLA Interim Groundwater Remediation for Chromium .....	2.5-3
2.5.2.1	Pump-and-Treat System.....	2.5-3
2.5.2.2	In Situ Redox Manipulation System.....	2.5-4
2.6	100-HR-3-H Operable Unit .....	2.6-1
2.6.1	Groundwater Contaminants .....	2.6-1
2.6.1.1	Chromium .....	2.6-1
2.6.1.2	Strontium-90.....	2.6-2
2.6.1.3	Technetium-99 and Uranium .....	2.6-2
2.6.1.4	Tritium .....	2.6-3
2.6.1.5	Nitrate .....	2.6-3
2.6.2	CERCLA Interim Groundwater Remediation for Chromium .....	2.6-3
2.6.2.1	Progress During Fiscal Year 2003 .....	2.6-3
2.6.2.2	Influence on Aquifer Conditions .....	2.6-3
2.6.3	RCRA Groundwater Monitoring for the 116-H-6 Evaporation Basins .....	2.6-4
2.7	100-FR-3 Operable Unit .....	2.7-1
2.7.1	Groundwater Contaminants .....	2.7-1
2.7.1.1	Nitrate .....	2.7-1
2.7.1.2	Strontium-90.....	2.7-2
2.7.1.3	Tritium .....	2.7-2
2.7.1.4	Trichloroethene .....	2.7-2
2.7.1.5	Gross Alpha and Gross Beta .....	2.7-2
2.7.1.6	Chromium .....	2.7-3
2.7.2	CERCLA Groundwater Monitoring .....	2.7-3
2.8	200-ZP-1 Operable Unit .....	2.8-1
2.8.1	Groundwater Contaminants .....	2.8-2
2.8.1.1	Carbon Tetrachloride.....	2.8-2
2.8.1.2	Trichloroethene .....	2.8-3
2.8.1.3	Chloroform .....	2.8-3
2.8.1.4	Nitrate .....	2.8-3
2.8.1.5	Chromium .....	2.8-4
2.8.1.6	Arsenic and Cadmium .....	2.8-4
2.8.1.7	Fluoride .....	2.8-5
2.8.1.8	Tritium .....	2.8-5
2.8.1.9	Iodine-129 .....	2.8-5

2.8.1.10	Technetium-99 .....	2.8-5
2.8.1.11	Uranium .....	2.8-6
2.8.2	CERCLA Interim Groundwater Remediation for Carbon Tetrachloride .....	2.8-6
2.8.2.1	Progress During Fiscal Year 2003 .....	2.8-7
2.8.2.2	Influence on Aquifer Conditions .....	2.8-8
2.8.3	RCRA Groundwater Monitoring .....	2.8-8
2.8.3.1	Waste Management Area T .....	2.8-9
2.8.3.2	Waste Management Area TX-TY .....	2.8-10
2.8.3.3	Low-Level Waste Management Area 3 .....	2.8-11
2.8.3.4	Low-Level Waste Management Area 4 .....	2.8-12
2.8.4	AEA Monitoring .....	2.8-13
2.8.4.1	Waste Management Areas T and TX-TY .....	2.8-13
2.8.4.2	Low-Level Waste Management Area 3 .....	2.8-16
2.8.4.3	Low-Level Waste Management Area 4 .....	2.8-16
2.8.5	Groundwater Monitoring for the State-Approved Land Disposal Site .....	2.8-17
2.9	200-UP-1 Operable Unit.....	2.9-1
2.9.1	Groundwater Contaminants .....	2.9-2
2.9.1.1	Technetium-99 .....	2.9-2
2.9.1.2	Uranium .....	2.9-2
2.9.1.3	Tritium .....	2.9-3
2.9.1.4	Iodine-129 .....	2.9-3
2.9.1.5	Strontium-90 .....	2.9-4
2.9.1.6	Chlorinated Hydrocarbons .....	2.9-4
2.9.1.7	Chromium .....	2.9-4
2.9.1.8	Nitrate .....	2.9-5
2.9.1.9	Other Constituents .....	2.9-5
2.9.2	CERCLA Groundwater Monitoring .....	2.9-6
2.9.2.1	Interim Groundwater Remediation for Technetium-99 and Uranium .....	2.9-6
2.9.2.2	Groundwater Monitoring at the Environmental Restoration Disposal Facility .....	2.9-8
2.9.3	RCRA Groundwater Monitoring .....	2.9-9
2.9.3.1	216-U-12 Crib .....	2.9-9
2.9.3.2	Waste Management Area U .....	2.9-10
2.9.3.3	Waste Management Area S-SX .....	2.9-11
2.9.3.4	216-S-10 Pond and Ditch .....	2.9-15
2.9.4	AEA Monitoring .....	2.9-16
2.9.4.1	Waste Management Area U .....	2.9-16
2.9.4.2	Waste Management Area S-SX .....	2.9-16
2.10	200-BP-5 Operable Unit .....	2.10-1
2.10.1	Groundwater Contaminants .....	2.10-2
2.10.1.1	Tritium .....	2.10-2
2.10.1.2	Nitrate .....	2.10-3
2.10.1.3	Iodine-129 .....	2.10-3
2.10.1.4	Technetium-99 .....	2.10-3
2.10.1.5	Cobalt-60 and Cyanide .....	2.10-4
2.10.1.6	Uranium .....	2.10-5
2.10.1.7	Cesium-137 and Strontium-90 .....	2.10-5
2.10.1.8	Plutonium .....	2.10-6
2.10.1.9	Other Constituents .....	2.10-6
2.10.2	CERCLA Groundwater Monitoring .....	2.10-6

2.10.3	RCRA Groundwater Monitoring .....	2.10-7
2.10.3.1	Waste Management Area B-BX-BY .....	2.10-7
2.10.3.2	216-B-63 Trench .....	2.10-8
2.10.3.3	Low-Level Waste Management Area 1 .....	2.10-8
2.10.3.4	Low-Level Waste Management Area 2 .....	2.10-9
2.10.3.5	Liquid Effluent Retention Facility .....	2.10-10
2.10.3.6	Waste Management Area C .....	2.10-10
2.10.4	AEA Monitoring .....	2.10-11
2.10.4.1	Waste Management Area B-BX-BY .....	2.10-11
2.10.4.2	Low-Level Waste Management Area 1 .....	2.10-12
2.10.4.3	Low-Level Waste Management Area 2 .....	2.10-13
2.10.4.4	Waste Management Area C .....	2.10-14
2.11	200-PO-1 Operable Unit.....	2.11-1
2.11.1	Groundwater Contaminants .....	2.11-2
2.11.1.1	Tritium .....	2.11-2
2.11.1.2	Iodine-129 .....	2.11-3
2.11.1.3	Nitrate .....	2.11-3
2.11.1.4	Strontium-90.....	2.11-3
2.11.1.5	Technetium-99 .....	2.11-4
2.11.1.6	Manganese .....	2.11-4
2.11.1.7	Other Constituents .....	2.11-4
2.11.2	CERCLA Groundwater Monitoring .....	2.11-4
2.11.3	RCRA Groundwater Monitoring .....	2.11-5
2.11.3.1	PUREX Cribs .....	2.11-6
2.11.3.2	Waste Management Area A-AX .....	2.11-6
2.11.3.3	216-A-29 Ditch.....	2.11-7
2.11.3.4	Integrated Disposal Facility .....	2.11-8
2.11.3.5	216-B-3 Pond Facility .....	2.11-9
2.11.3.6	Nonradioactive Dangerous Waste Landfill .....	2.11-10
2.11.4	AEA Monitoring .....	2.11-11
2.11.4.1	Waste Management Area A-AX .....	2.11-11
2.11.4.2	400 Area Water Supply Wells .....	2.11-12
2.11.5	Washington Administrative Code .....	2.11-12
2.11.5.1	200 Area Treated Effluent Disposal Facility .....	2.11-13
2.11.5.2	Solid Waste Landfill .....	2.11-13
2.11.5.3	400 Area Process Ponds .....	2.11-16
2.12	300-FF-5 Operable Unit .....	2.12-1
2.12.1	Groundwater Contaminants .....	2.12-2
2.12.1.1	Uranium .....	2.12-2
2.12.1.2	Chlorinated Hydrocarbons .....	2.12-3
2.12.1.3	Strontium-90.....	2.12-4
2.12.1.4	Tributyl Phosphate .....	2.12-4
2.12.1.5	Nitrate .....	2.12-5
2.12.1.6	Tritium .....	2.12-5
2.12.1.7	Petroleum Hydrocarbons .....	2.12-6
2.12.2	CERCLA Groundwater Monitoring and Interim Action .....	2.12-6
2.12.3	RCRA Groundwater Monitoring at the 316-5 Process Trenches .....	2.12-8
2.13	1100-EM-1 Operable Unit .....	2.13-1
2.13.1	Groundwater Contaminants .....	2.13-1
2.13.1.1	Chlorinated Hydrocarbons .....	2.13-2
2.13.1.2	Tritium .....	2.13-2

2.13.1.3	Nitrate .....	2.13-3
2.13.1.4	Gross Alpha and Uranium .....	2.13-3
2.13.1.5	Other Constituents .....	2.13-4
2.13.2	CERCLA Groundwater Monitoring .....	2.13-4
2.14	Confined Aquifers .....	2.14-1
2.14.1	Ringold Formation Confined Aquifer .....	2.14-1
2.14.1.1	Groundwater Flow in the Ringold Formation Confined Aquifer .....	2.14-1
2.14.1.2	Groundwater Quality in the Ringold Confined Aquifer .....	2.14-2
2.14.2	Upper Basalt-Confined Aquifer .....	2.14-2
2.14.2.1	Groundwater Flow in the Upper Basalt-Confined Aquifer .....	2.14-3
2.14.2.2	Groundwater Quality in the Upper Basalt-Confined Aquifer .....	2.14-4
3.0	Vadose Zone .....	3.0-1
3.1	Vadose Zone Characterization .....	3.1-1
3.1.1	Tank Farm Characterization .....	3.1-1
3.1.1.1	Characterization at Waste Management Area T .....	3.1-1
3.1.1.2	Characterization at Waste Management Area TX-TY .....	3.1-2
3.1.1.3	Summary of Significant Findings from the Field Investigation Report for Waste Management Area B-BX-BY .....	3.1-3
3.1.2	Borehole Geophysics for Vadose Zone Characterization .....	3.1-4
3.1.3	Characterization at the 200-PW-1 Operable Unit .....	3.1-6
3.1.4	Characterization of the 200-CS-1 Operable Unit .....	3.1-7
3.1.5	300 Area Uranium Leach and Adsorption Studies.....	3.1-8
3.2	Vadose Zone Monitoring .....	3.2-1
3.2.1	Leachate and Soil-Gas Monitoring at the Solid Waste Landfill .....	3.2-1
3.2.2	Leachate Monitoring at the Environmental Restoration Disposal Facility .....	3.2-2
3.2.3	Vadose Zone Monitoring at Single-Shell Tank Farms .....	3.2-3
3.2.4	Carbon Tetrachloride Monitoring and Remediation .....	3.2-4
3.2.4.1	Soil-Vapor Extraction .....	3.2-5
3.2.4.2	Monitoring at Off-Line Wells and Probes .....	3.2-5
3.2.4.3	Passive Soil-Vapor Extraction .....	3.2-6
3.3	Vadose Zone Studies .....	3.3-1
3.3.1	Field Lysimeter Test Facility .....	3.3-1
3.3.2	Vadose Zone Water Fluxmeter Improvements and Tests .....	3.3-4
3.3.3	Mineralogical and Bulk-Rock Geochemical Signatures of Ringold and Hanford Formation Sediment .....	3.3-5
3.3.4	Isotopic Investigation of Vadose Zone Pore Water .....	3.3-5
3.3.5	Hydrologic Performance of a Prototype 1,000-Year Hanford Barrier .....	3.3-7
3.3.6	STOMP-Based Tool to Optimize Surface Barrier Design .....	3.3-8
3.3.7	Impact of Clastic Dikes on Vadose Zone Flow .....	3.3-10
4.0	Groundwater Modeling .....	4.0-1
4.1	Site-Wide Groundwater Flow and Transport Model .....	4.0-1
4.1.1	Development and Calibration of Alternative Conceptual Model 2 .....	4.0-1
4.1.2	Background Information on the Site-Wide Groundwater Model .....	4.0-2
4.2	System Assessment Capability .....	4.0-3
4.3	Local-Scale Modeling of Pump-and-Treat Systems .....	4.0-3

5.0	Well Installation, Maintenance, and Decommissioning.....	5.0-1
5.1	Well Installation .....	5.0-1
5.2	Well Maintenance .....	5.0-2
5.3	Well Decommissioning.....	5.0-3
6.0	References .....	6.0-1
Appendix A	- Supporting Information for CERCLA Groundwater Operable Units .....	A.1
Appendix B	- Supporting Information for RCRA Units .....	B.1
Appendix C	- Supporting Information for Other Regulated Sites .....	C.1
Appendix D	- Quality Assurance and Quality Control .....	D.1

## Tables

1.1-1	Regulated Units and Groundwater Operable Units on the Hanford Site .....	1.0-4
2.1-1	Number of Groundwater Analyses by Groundwater Interest Area, Fiscal Year 2003 .....	2.1-6
2.1-2	Maximum Concentrations of Selected Groundwater Contaminants in Fiscal Year 2003 .....	2.1-7
2.9-1	Summary of Contaminant Mass Removed from the Aquifer during Pump-and-Treat Operations at the 200-UP-1 Operable Unit - Fiscal Year 2003 and Totals Since Startup of Operations .....	2.9-18
2.9-2	Vertical Variation of Groundwater Composition Measured in the Wellbore of Well 299-W23-19 and Estimated for the Adjacent Aquifer During the End of a 4,013-Liter Purge on September 23, 2003 .....	2.9-18
2.9-3	Quantity of Treated Groundwater and Technetium-99 Mass Removed from the Aquifer During Extended Purging at Well 299-W23-19 .....	2.9-18
2.11-1	Ranges of Reported Volatile Organic Compound Concentrations in Solid Waste Landfill Wells During Fiscal Year 2003 .....	2.11-18
2.14-1	Potential Contaminants in Ringold Confined Aquifer, Fiscal Years 2001 through 2003 .....	2.14-6
2.14-2	Potential Contaminants in Upper Basalt-Confined Aquifer, Fiscal Years 2001 through 2003 .....	2.14-7
3.1-1	Summary of Significant Borehole Logging Results from Fiscal Year 2003 Characterization Boreholes at the T and TX Tank Farms .....	3.1-11
3.1-2	Selective Extraction Results for Uranium in Six Near-Surface Sediment Samples .....	3.1-11
3.2-1	Carbon Tetrachloride Inventory in Primary Disposal Sites .....	3.2-7
5.1-1	Well Installations for Calendar Year 2003 .....	5.0-4
5.1-2	Vadose Characterization Wells, Soil-Gas Probes, and GeoProbe/Push Installations for Fiscal Year 2003 .....	5.0-5
5.2-1	Well Maintenance Summary for Fiscal Year 2003 .....	5.0-6
5.3-1	Wells Decommissioned During Fiscal Year 2003 .....	5.0-7

---

# Figures

2.1-1	Groundwater Operable Units and Groundwater Interest Areas on the Hanford Site .....	2.1-9
2.1-2	Groundwater Monitoring Wells in the 600 Area .....	2.1-11
2.1-3	Hanford Site and Outlying Areas Water-Table Map, March 2003 .....	2.1-13
2.1-4	Water Level in Well 299-E32-8, Northwest 200 East Area .....	2.1-14
2.1-5	Average Fiscal Year 2003 Tritium Concentrations on the Hanford Site, Top of Unconfined Aquifer .....	2.1-15
2.1-6	Average Fiscal Year 2003 Nitrate Concentrations on the Hanford Site, Top of Unconfined Aquifer .....	2.1-16
2.1-7	Average Fiscal Year 2003 Iodine-129 Concentrations on the Hanford Site, Top of Unconfined Aquifer .....	2.1-17
2.1-8	Dissolved Chromium at Selected Aquifer Tube Sites for Selected Years, 100 Areas .....	2.1-18
2.2-1	Groundwater Monitoring Wells in the 100-B/C Area .....	2.2-4
2.2-2	100-B/C Area Water-Table Map, March 2003 .....	2.2-5
2.2-3	Average Strontium-90 Concentrations in the 100-B/C Area, Top of Unconfined Aquifer .....	2.2-6
2.2-4	Strontium-90 Concentrations and Water Levels Near 116-C-1 Trench .....	2.2-7
2.2-5	Strontium-90 Concentrations and Water Levels Near 116-B-1 Trench .....	2.2-7
2.2-6	Tritium Concentrations Near 116-B-11 Retention Basin, and Near 118-B-1 Burial Ground .....	2.2-8
2.2-7	Tritium Concentrations East of 100-B/C Area .....	2.2-8
2.3-1	Location Map for 100-K Area Facilities, Waste Sites, Monitoring Wells, and Shoreline Monitoring Sites .....	2.3-9
2.3-2	Chromium Distribution in 100-K Area Groundwater, Fiscal Year 2003 .....	2.3-10
2.3-3	Chromium Concentrations in Pump-and-Treat Performance Monitoring Wells .....	2.3-11
2.3-4	Increasing Chromium Concentrations at the Southwest Edge of Plume Associated with the 116-K-2 Trench .....	2.3-12
2.3-5	Chromium Concentrations Near KE Water Treatment Plant Basins .....	2.3-12
2.3-6	Chromium Concentrations Near KW Reactor .....	2.3-13
2.3-7	Tritium Distribution in 100-K Area Groundwater, Fiscal Year 2003 .....	2.3-14
2.3-8	Tritium and Carbon-14 Concentrations Near the 116-KE-1 Crib .....	2.3-15
2.3-9	Tritium Concentrations Near KE Basin .....	2.3-15
2.3-10	Tritium and Carbon-14 Concentrations Near the 116-KW-1 Crib .....	2.3-16
2.3-11	Tritium Concentrations Near KW Basin .....	2.3-16
2.3-12	Tritium Concentrations Near 118-K-1 Burial Ground .....	2.3-17
2.3-13	Helium Isotope Ratios in Soil Gas Near 118-K-1 Burial Ground .....	2.3-18
2.3-14	Strontium-90 and Gross Beta Concentrations Near KE Basin .....	2.3-19
2.3-15	Tritium Concentrations in Wells Downgradient of the Pump-and-Treat Injection Site .....	2.3-19
2.4-1	Groundwater Monitoring Wells in the 100-N Area .....	2.4-7
2.4-2	Water Table Beneath 100-N Area, March 2003 .....	2.4-8
2.4-3	Average Strontium-90 Concentrations in the 100-N Area, Top of Unconfined Aquifer .....	2.4-9
2.4-4	Strontium-90 Concentrations and Water Level Near the 116-N-1 Facility .....	2.4-10

2.4-5	Average Tritium Concentrations in the 100-N Area, Top of the Unconfined Aquifer .....	2.4-11
2.4-6	Tritium Concentrations North of the 116-N-1 Facility .....	2.4-12
2.4-7	Nitrate Concentrations and Water Level Near the 116-N-1 Facility .....	2.4-12
2.4-8	Average Sulfate Concentrations in the 100-N Area, Top of Unconfined Aquifer .....	2.4-13
2.4-9	Sulfate Concentrations in 100-N Area Wells .....	2.4-14
2.4-10	Petroleum Hydrocarbons Near Former Petroleum Leak Site .....	2.4-14
2.4-11	Strontium-90 Concentrations in 100-N Area Extraction Wells .....	2.4-15
2.5-1	Groundwater Monitoring Wells in the 100-D Area .....	2.5-6
2.5-2	Groundwater Monitoring Wells Near the Redox Site in 100-D Area .....	2.5-7
2.5-3	100-D Area Water-Table Map, March 2003 .....	2.5-8
2.5-4	Average Dissolved Chromium Concentrations in the 100-D Area, Top of Unconfined Aquifer .....	2.5-9
2.5-5	Average Dissolved Chromium Concentrations Near the Redox Site, 100-D Area, August-September 2003 .....	2.5-10
2.5-6	Dissolved Chromium Concentrations in South 100-D Area .....	2.5-11
2.5-7	Dissolved Chromium Concentrations in Compliance Wells Downgradient of Early-Emplaced Redox Barrier .....	2.5-11
2.5-8	Dissolved Chromium Concentrations in Compliance Wells Downgradient of Late-Emplaced Redox Barrier .....	2.5-12
2.5-9	Hexavalent Chromium in Aquifer Tubes at 100-D Area, Fiscal Year 2003 .....	2.5-12
2.5-10	Dissolved Chromium Concentrations in Central 100-D Area .....	2.5-13
2.5-11	Tritium Concentrations in the South 100-D Area .....	2.5-13
2.5-12	Sulfate Concentrations Downgradient of the Redox Barrier .....	2.5-14
2.5-13	Dissolved Chromium Concentrations in Compliance Wells for the 100-HR-3 Pump-and-Treat System at 100-D Area .....	2.5-14
2.6-1	Groundwater Monitoring Wells in the 100-H Area .....	2.6-5
2.6-2	Water Table Beneath 100-H Area, March 2003 .....	2.6-6
2.6-3	Average Chromium Concentrations in the 100-H Area, Top of Unconfined Aquifer .....	2.6-7
2.6-4	Dissolved Chromium Concentrations East of 116-H-6 Evaporation Basins .....	2.6-8
2.6-5	Technetium-99 Concentrations East of 116-H-6 Evaporation Basins .....	2.6-8
2.6-6	Technetium-99 and Uranium Concentrations Northeast of 116-H-6 Evaporation Basins .....	2.6-9
2.6-7	Average Nitrate Concentrations in the 100-H Area, Top of Unconfined Aquifer .....	2.6-10
2.6-8	Dissolved Chromium Concentrations in a Compliance Wells for the 100-HR-3 Pump-and-Treat System at 100-H Area .....	2.6-11
2.7-1	Groundwater Monitoring Wells in the 100-F Area .....	2.7-4
2.7-2	100-F Area Water-Table Map, March 2003 .....	2.7-5
2.7-3	Nitrate Concentrations in Southeast and Southwest 100-F Area .....	2.7-6
2.7-4	Nitrate Concentrations Southwest and South of 100-F Area .....	2.7-6
2.7-5	Strontium-90 Concentrations and Water Levels in East 100-F Area .....	2.7-7
2.7-6	Tritium Concentrations Near 118-F-6 Burial Ground .....	2.7-7
2.7-7	Trichloroethene in the Southwest 100-F Area .....	2.7-8
2.8-1	Groundwater Monitoring Wells in the 200 West Area .....	2.8-19
2.8-2	Water-Table Contours in the 200 West Area .....	2.8-21

2.8-3	Average Carbon Tetrachloride Concentrations in 200 West Area, Top of Unconfined Aquifer.....	2.8-23
2.8-4	Carbon Tetrachloride Concentrations Northeast of the 200 West Area in Well 699-48-71 ....	2.8-25
2.8-5	Average Trichloroethene Concentrations in Central and North 200 West Area, Top of Unconfined Aquifer .....	2.8-26
2.8-6	Average Nitrate Concentrations in the Central and North 200 West Area, Top of Unconfined Aquifer .....	2.8-27
2.8-7	Average Dissolved Chromium Concentrations Near Waste Management Area T and TX-TY, Top of Unconfined Aquifer .....	2.8-28
2.8-8	Average Fluoride Concentrations in North 200 West Area, Top of Unconfined Aquifer .....	2.8-29
2.8-9	Average Tritium Concentrations in the North 200 West Area, Top of Unconfined Aquifer ...	2.8-30
2.8-10	Tritium Concentrations versus Time in Wells 299-W14-12 and 299-W14-13 at Waste Management Area TX-TY .....	2.8-31
2.8-11	Average Iodine-129 Concentrations in the North 200 West Area, Top of Unconfined Aquifer.....	2.8-32
2.8-12	Average Technetium-99 Concentrations in the North 200 West Area, Top of Unconfined Aquifer .....	2.8-33
2.8-13	Technetium-99 Concentrations in Selected Wells at Waste Management Area T .....	2.8-34
2.8-14	Carbon Tetrachloride Concentrations at Extraction Well 299-W15-32, Near the 216-Z-9 Trench .....	2.8-34
2.8-15	Chromium Concentrations versus Time for Selected Upgradient Wells at Waste Management Area T .....	2.8-35
2.8-16	Chromium Concentration versus Time for Selected Wells North of Waste Management Area T .....	2.8-35
2.8-17	Chromium and Technetium-99 Concentrations versus Time for Selected Wells Downgradient of Waste Management T .....	2.8-36
2.8-18	Chromium Concentrations in Well 299-W14-13, East of Waste Management Area TX-TY .....	2.8-36
2.8-19	Nickel Concentrations in Well 299-W7-1, North of Low-Level Waste Management Area 3 .....	2.8-37
2.8-20	Specific Conductance versus Depth Below the Water Table in Well 299-W10-28 .....	2.8-37
2.8-21	Specific Conductance versus Depth in the Screened Interval of Well 299-W14-13 .....	2.8-38
2.8-22	Nitrate Concentration in Groundwater Samples Collected During Drilling of New RCRA Well 299-W15-44, Waste Management Area TX-TY .....	2.8-38
2.8-23	Concentrations of Selected Constituents versus Depth in the Screened Interval of Well 299-W14-13 at Waste Management Area TX-TY .....	2.8-39
2.8-24	Tritium Concentrations in Groundwater for the SALDS Tritium-Tracking Network, Fiscal Year 2003, Indicating Changes from Fiscal Year 2002 Results .....	2.8-40
2.9-1	Facilities and Groundwater Monitoring Wells in the 200 West Area .....	2.9-19
2.9-2	Average Technetium-99 Concentrations in the 200-UP-1 Groundwater Interest Area, Top of Unconfined Aquifer .....	2.9-21
2.9-3	Technetium-99 Concentrations at Waste Management Area S-SX .....	2.9-22
2.9-4	Average Uranium Concentrations in the 200-UP-1 Groundwater Interest Area, Top of Unconfined Aquifer .....	2.9-23
2.9-5	Average Tritium Concentrations in the 200-UP-1 Groundwater Interest Area, Top of Unconfined Aquifer .....	2.9-25

2.9-6	Average Iodine-129 Concentrations in the 200-UP-1 Groundwater Interest Area, Top of Unconfined Aquifer .....	2.9-27
2.9-7	Average Nitrate Concentrations in the 200-UP-1 Groundwater Interest Area, Top of Unconfined Aquifer .....	2.9-29
2.9-8	Technetium-99 Concentrations in Extraction and Monitoring Wells at the 200-UP-1 Pump-and-Treat Area .....	2.9-31
2.9-9	Uranium Concentrations in Extraction and Monitoring Wells at the 200-UP-1 Pump-and-Treat Area .....	2.9-31
2.9-10	Average Technetium-99 Concentrations in the 200-UP-1 Pump-and-Treat Area, Top of Unconfined Aquifer .....	2.9-32
2.9-11	Average Uranium Concentrations in the 200-UP-1 Pump-and-Treat Area, Top of Unconfined Aquifer .....	2.9-33
2.9-12	Average Nitrate Concentrations at Waste Management Area S-SX, Top of Unconfined Aquifer .....	2.9-34
2.9-13	Average Chromium Concentrations at Waste Management Area S-SX, Top of Unconfined Aquifer .....	2.9-35
2.9-14	Wellbore-Fluid Specific Conductance Logs Collected in Well 299-W23-19 at Waste Management Area S-SX .....	2.9-36
2.9-15	Wellbore-Fluid Specific Conductance Measurements Collected in Well 299-W23-19 at Waste Management Area S-SX .....	2.9-36
2.9-16	Wellbore-Fluid Specific Conductance Measurements Collected during Sampling on September 23, 2003 in Well 299-W23-19 .....	2.9-37
2.9-17	Chromium Concentrations Near the 216-S-10 Pond and Ditch .....	2.9-37
2.9-18	Chromium and Nitrate Concentrations in Well 299-W26-7 Near the 216-S-10 Pond and Ditch .....	2.9-38
2.9-19	Average Technetium-99 Concentrations at Waste Management Area S-SX, Top of Unconfined Aquifer .....	2.9-39
2.9-20	Average Tritium Concentrations at Waste Management Area S-SX, Top of Unconfined Aquifer .....	2.9-40
2.10-1	Groundwater Monitoring Wells in the 200 East Area .....	2.10-15
2.10-2	Groundwater Monitoring Wells Located in the 600 Area Associated with the 200-BP-5 Operable Unit .....	2.10-17
2.10-3	Average Tritium Concentrations in the 200-BP-5 Operable Unit and Vicinity, Top of Unconfined Aquifer .....	2.10-18
2.10-4	Average Nitrate Concentrations in the 200-BP-5 Operable Unit and Vicinity, Top of Unconfined Aquifer .....	2.10-19
2.10-5	Average Iodine-129 Concentrations in the 200-BP-5 Operable Unit and Vicinity, Top of Unconfined Aquifer .....	2.10-20
2.10-6	Average Technetium-99 Concentrations in the North 200 East Area, Top of Unconfined Aquifer .....	2.10-21
2.10-7	Technetium-99 Concentrations in Wells 299-E33-7 and 299-E33-38 at the BY Cribs and Well 699-49-57A North of 200 East Area .....	2.10-22
2.10-8	Average Uranium Concentrations in the Vicinity of BY Cribs, Top of Unconfined Aquifer ...	2.10-23
2.10-9	Strontium-90 Concentrations in Wells 299-E28-23 and 299-E28-25 at the 216-B-5 Injection Well Site .....	2.10-24
2.10-10	Strontium-90 Concentrations at Gable Mountain Pond, Top of Unconfined Aquifer .....	2.10-25

2.10-11	Hydrograph for Wells at Waste Management Area B-BX-BY Showing the Distinct Increase in Water Levels .....	2.10-26
2.10-12	Nitrate Concentrations in Low-Level Waste Management Area 2 Wells 299-E34-7, 299-E27-10, and 299-E27-9 .....	2.10-26
2.10-13	Trend Plots of Technetium-99 Concentrations at Waste Management Area B-BX-BY .....	2.10-27
2.10-14	Technetium-99 Concentrations Compared to Nitrate Concentrations for Upgradient Well 299-E27-7 at Waste Management C .....	2.10-27
2.11-1	Groundwater Monitoring Wells in the 200 East Area .....	2.11-19
2.11-2	Tritium Concentrations at the 216-A-36B Crib, Well 299-E17-14 .....	2.11-21
2.11-3	Tritium Concentrations at the 216-A-36B Crib, Well 299-E17-9 .....	2.11-21
2.11-4	Iodine-129 Concentrations at the 216-A-36B Crib, Well 299-E17-14 .....	2.11-22
2.11-5	Iodine-129 Concentrations at the 216-A-10 Crib, Well 299-E17-1 .....	2.11-22
2.11-6	Nitrate Concentrations at Upgradient Well 299-E24-18 for the PUREX Cribs .....	2.11-23
2.11-7	Nitrate Concentrations at the 216-A-36B Crib, Well 299-E17-14 .....	2.11-23
2.11-8	Strontium-90 Concentrations at the 216-A-36B Crib .....	2.11-24
2.11-9	Manganese Concentrations at the 216-A-10 Crib .....	2.11-24
2.11-10	Specific Conductance in Wells Monitoring Waste Management Area A-AX .....	2.11-25
2.11-11	Groundwater Monitoring Wells at the Central Landfill and Vicinity .....	2.11-26
2.11-12	Total Organic Carbon Concentrations at Upgradient Well 699-26-35A, Shared by the Solid Waste Landfill and Nonradioactive Dangerous Waste Landfill .....	2.11-27
2.11-13	Chromium and Technetium-99 Trends at Waste Management Area AX, Well 299-E24-19 ....	2.11-27
2.11-14	Chromium and Technetium-99 Trends at Waste Management Area A-AX, Well 299-E25-46 .....	2.11-28
2.11-15	Groundwater Monitoring Wells in the 400 Area .....	2.11-29
2.11-16	Comparison of Tritium Concentrations in 400 Area Drinking Water Wells .....	2.11-30
2.11-17	Average Nitrate Concentrations in 400 Area Process Pond Area, Top of Unconfined Aquifer .....	2.11-31
2.11-18	Nitrate Concentrations in Wells Monitoring the 400 Area Process Ponds .....	2.11-32
2.12-1	Groundwater Monitoring Wells in the Richland North and 300 Areas .....	2.12-9
2.12-2	Subdivisions of the 300-FF-5 Operable Unit .....	2.12-11
2.12-3	Groundwater Flow Direction in the Richland North and 300 Areas .....	2.12-13
2.12-4	Uranium Concentrations in the Richland North and 300 Areas, December 2002, Top of Unconfined Aquifer .....	2.12-15
2.12-5	Uranium Concentrations in the Richland North and 300 Areas, June 2003, Top of Unconfined Aquifer .....	2.12-16
2.12-6	300 Area Wells Showing Long-Term Gradual Decline in Uranium Concentrations Since 1997 .....	2.12-17
2.12-7	300 Area Wells Showing Increases in Uranium Concentrations Until 2000 .....	2.12-18
2.12-8	Uranium Concentrations in Well 399-1-10A .....	2.12-19
2.12-9	Uranium Concentrations in Well 399-8-5A .....	2.12-19
2.12-10	Location of Monitoring Wells in the 300 North Area .....	2.12-20
2.12-11	Average Trichloroethene Concentrations in the Richland North and 300 Areas, Top of Unconfined Aquifer .....	2.12-21
2.12-12	Trichloroethene and cis-1,2-Dichloroethene Concentrations in Well 399-1-16B .....	2.12-22

2.12-13	Nitrate Concentrations in the Richland North and 300 Areas .....	2.12-23
2.12-14	Average Tritium Concentrations in Groundwater in the Richland North and 300 Areas, Top of Unconfined Aquifer .....	2.12-25
2.12-15	Tritium Concentrations in Wells Monitoring the 300 Area .....	2.12-26
2.12-16	Tritium Concentrations at Well 699-13-3A Near 618-11 Burial Ground .....	2.12-27
2.12-17	Tritium Concentrations During 2003 in Plume Associated with the 618-11 Burial Ground .....	2.12-27
2.13-1	Trichloroethene Concentrations Near the U.S. Department of Energy's Inactive Horn Rapids Landfill .....	2.13-6
2.13-2	Tritium Concentrations in Wells Monitoring the 1100-EM-1 Groundwater Interest Area .....	2.13-6
2.13-3	Nitrate Concentrations in Wells Monitoring the 1100-EM-1 Groundwater Interest Area .....	2.13-7
2.13-4	Uranium Concentrations Near the U.S. Department of Energy's Inactive Horn Rapids Landfill .....	2.13-7
2.14-1	Potentiometric Surface Map of Ringold Formation Confined Aquifer, Central Hanford Site, March 2003 .....	2.14-8
2.14-2	Groundwater Monitoring Wells Sampled in the Ringold and Upper Basalt-Confined Aquifers, Fiscal Years 2001 through 2003 .....	2.14-9
2.14-3	Potentiometric Surface Map of Upper Basalt-Confined Aquifer System, March 2003 .....	2.14-10
2.14-4	Distribution of Chemical and Radiological Constituents in the Upper Basalt-Confined Aquifer, Fiscal Years 2001 through 2003 .....	2.14-11
3.1-1	Electrical Conductivity and pH versus Depth in Characterization Borehole C3831 at the TX Tank Farm .....	3.1-12
3.1-2	Concentrations of Contaminant Indicators Technetium-99, Nitrate, and Sodium versus Depth in Characterization Boreholes at TX Tank Farm .....	3.1-13
3.1-3	Cobalt-60 Contamination in the Vadose Zone Near Waste Management Area B-BX-BY .....	3.1-14
3.1-4	Uranium-238 Contamination in the Vadose Zone Near Waste Management Area B-BX-BY .....	3.1-15
3.1-5	Locations of Boreholes and Test Pits for Characterization of the 216-A-29 Ditch and 216-B-63 Trench .....	3.1-16
3.1-6	Locations of Borehole B8828 and Test Pits at the 216-S-10 Ditch and Pond System .....	3.1-17
3.2-1	Leachate Collection Volumes at the Solid Waste Landfill .....	3.2-8
3.2-2	Locations of Carbon Tetrachloride Vapor-Extraction Wells at the 216-Z-1A/216-Z-12/216-Z-18 and the 216-Z-9 Well Fields .....	3.2-9
3.2-3	Time Series Concentrations and Mass of Carbon Tetrachloride in Soil Vapor Extracted from the 216-Z-1A/216-Z-12/216-Z-18 Well Field .....	3.2-10
3.3-1	View of the Field Lysimeter Test Facility Looking Southwest Toward Rattlesnake Mountain .....	3.3-11
3.3-2	Drawing of the Field Lysimeter Test Facility .....	3.3-12
3.3-3	Water Fluxmeter with Solution Collection Capability .....	3.3-13
3.3-4	Water Fluxmeter Data Showing Drainage from Soil Materials Tested at the Hanford Site .....	3.3-13
3.3-5	Temporal Variation in Mean Soil Water Storage on the North and South Plots at the Prototype Hanford Barrier, November 1994 through September 2003 .....	3.3-14
3.3-6	Cumulative Amounts of Water Diverted by the Asphalt Pad from the Side-Slope Plots at the Prototype Hanford Barrier in September 1994 through September 2003 .....	3.3-14
3.3-7	Primary Environmental Interactions Governing Functional Performance of a Typical 1,000-Year Capillary Barrier .....	3.3-15

---

3.3-8	Simulated Aqueous Saturation as a Function of Depth within a Layered Soil .....	3.3-15
3.3-9	STOMP Simulated Air and Soil Surface Temperature for Water and Heat Flow in a Layered Soil System Typical of a Capillary Barrier .....	3.3-16
4.1-1	Facies Zones Defined for Alternative Conceptual Model 2, Unit 1 .....	4.0-5
4.1-2	Facies Zones Defined for Alternative Conceptual Model 2, Unit 5 .....	4.0-6
4.1-3	Runoff Areas Applied to Model Elements Updated System Assessment Capability Model Grid .....	4.0-7
4.1-4	Updated System Assessment Capability Model Grid .....	4.0-8
5.1-1	Groundwater Monitoring Wells Installed in Calendar Year 2003 .....	5.0-8